

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

<i>Items of work</i>	<i>Per</i>	<i>Quantity</i>
In-patient Ward—		
Earthwork excavating and filling basement ...	C. yd.	176
Concrete in chunam ...	C. ft.	1,066
Burnt stone in chunam ...	"	2,509
Burnt brick in chunam ...	"	3,263
Stone slabs, 6" thick, dressed ...	S. ft.	690
Pointing with chunam ...	Sq.	3.30
Plastering with chunam ...	"	52.17
Flooring with Cuddapah slabs 1½" thick over 3" concrete and cement pointing, etc., complete ...	"	7.56
Flooring with Mangalore square tiles over 3" concrete and cement pointing ...	"	3.75
Roofing with 1st class Mangalore tiles with teak reepers, 2" × 1", etc., complete ...	"	28.13
Ridge and high tiles set in mortar ...	R. ft.	126
Ventilating tiles ...	No.	8
Teakwood work with wood oiling ...	C. ft.	162.41
Teakwood panelled doors ...	S. ft.	267
Teakwood panelled windows, outside and glazed inside with iron bars, complete ...	"	63
Teakwood glazed ventilators with iron bars ...	"	81
Iron clamps for doors, windows and ventilators ...	No.	80
Teakwood ornamental eave boards with painting ...	R. ft.	305
Ornamental large boards including finials ...	No.	3
Zinc gutters to valleys ...	"	3
Sun shades ...	"	3
White and colorwashing ...	Sq.	52.17
Painting to doors and windows ...	"	8.04
Teakwood ceiling ...	"	6.62
Teakwood pillars including bases, capitals and painting, etc., complete ...	No.	11
Clearing site and levelling ground ...	L. S.	12
Kitchen—		
Excavating and filling ...	C. yd.	21
Stone in chunam ...	C. ft.	735
Burnt brick in mud ...	"	776
Plastering with chunam ...	Sq.	15.42
Painting do ...	"	1.09
Burnt stone slabs with dressing ...	S. ft.	87
Whitewashing ...	Sq.	15.42
Honnewoot work with wood oiling ...	C. ft.	25.28
Roofing with 1st class Mangalore tiles with teak reepers, complete ...	Sq.	6.25
Ridge tiles set in mortar ...	R. ft.	31
Honnewood doors battened with iron clamps ...	S. ft.	36
Do windows with iron bars, complete, with clamps ...	"	45
Flooring with Cuddapah slabs on 3" concrete with cement pointing ...	Sq.	2.64
Burnt brick in chunam ...	C. ft.	215
Chocolate painting ...	Sq.	162
Constructing a hearth and iron chimney with trowel ...	L. S.	

V. AIYASWAMI IYER,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

The attention of the public is invited to the notification dated 21st December 1911, calling for tenders for restoring Ammasandra tank, R. No. 236, Gubbi Taluk, Tumkur District.

Abstract Notification dated 28th December 1911.

Attention of the public is invited to notification dated 28th December 1911, published in page 36, calling for tenders for "Constructing second block of eight rooms to Students' Home at Tumkur."

Dated 4th January, 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 29th January 1912, for constructing 25 Barr huts at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing 25 Barr huts at Tumkur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable quantity for constructing 25 Barr huts (five blocks) at Tumkur.

(N. B.—The quantity for one hut is given below, the quantity for the other huts being the same.)

No.	Items of work	Per	Quantity
1.	Earthwork, excavating foundation	C. yd.	94
2.	Burnt stone in mud	C. ft.	2,929
3.	Burnt brick in mud	"	4,179
4.	Burnt brick in chunam	"	939
5.	Burnt stone slabs with one line dressed	S. ft.	490
6.	Plastering with mortar, rough outside	Sqr.	44.59
7.	Mud-plastering inside	"	53.85
8.	Chunam-pointing	"	1.18
9.	Color-washing	"	44.59
10.	Whitewashing	"	53.85
11.	Flooring with gravel	C. yd.	44
12.	Coping with brick in chunam and plastering	R. ft.	250
13.	Constructing V-shaped drain with slopes	"	74
14.	Honnewood work with wood-oiling	C. ft.	83.35
15.	Honnewood battened doors with iron clamps and painting, complete	S. ft.	429
16.	Honnewood battened windows with $\frac{3}{8}$ " diameter iron bars with iron clamps and painting, complete	"	90
17.	Roofing with first class Mangalore tiles, including teak reepers	Sqr.	23.68
18.	Ridge tiles set in mortar	R. ft.	74
19.	Ventilating or smoke tiles	Each	20
20.	Cornice, plain, at gable ends	R. ft.	60
21.	Clearing site and levelling ground and tarring wood work	L. S. Rupees.	
22.	Dwarf wall at gable ends with brick in chunam and plastering, complete	R. ft.	56
23.	Glazed tiles to each hut	Each	15
24.	Niches with two teak planks complete, two to each hut	"	10

K. PONNAPPA,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

It is hereby notified that sealed tenders for constructing a 3rd class travellers' bungalow at Aiyamangala, Hiriya Taluk, will be received by the Executive Engineer, Chitaldrug Division, up to 25th January 1912. For particulars, please see pages 37 and 38 of the *Mysore Gazette*, dated 4th January 1912.

C. KRISHNA IYENGAR,
Executive Engineer.
2 H.